

Nominal breakdown voltage $V_N$	400	V
Initial values		
Static breakdown voltage $V_S$ <sup>1) 2)</sup>		
First ignition value $V_{S, FTE}$ after 24 hours in darkness	$\leq 460$	V
Following ignition values (selection limits)	360 ... 420	V
Following ignition values $V_{S, FIV}$	350 ... 430	V
Breakdown voltage $V_B$ (measuring time 200 ms) <sup>4)</sup>		
First ignition value $V_{B, FTE}$	$\leq 460$	V
Following ignition values $V_{B, FIV}$	340 ... 460	V
Electrical life time <sup>3)</sup>		
Breakdown voltage $V_B$		
First ignition value $V_{B, FTE}$ initial after 24 hours in darkness	$\leq 460$	V
First ignition value $V_{B, FTE}$ after 24 hours in darkness	$\leq 500$	V
Following ignition values $V_{B, FIV}$	340 ... 460	V
Switching operations		
at - 40 °C            Ignition time $t_i \leq 60$ ms <sup>5)</sup>	60 000	Ignitions
at - 40 °C            Ignition time $t_i \leq 200$ ms	100 000	Ignitions
at +25 °C            Ignition time $t_i \leq 60$ ms	100 000	Ignitions
at +25 °C            Ignition time $t_i \leq 200$ ms	200 000	Ignitions
at +125 °C           Ignition time $t_i \leq 60$ ms	200 000	Ignitions
Test circuit parameters		
Open circuit voltage $V_0$	500	V
Loading resistance R	10	k $\Omega$
Discharge capacitance C	680	nF
Inductance L	0.5	$\mu$ H
Discharge peak current $I_P$	~ 500	A
General technical data		
Insulation resistance at 100 V	> 100	M $\Omega$
Early ignition values below 340 V	$\leq 2$	%
Breakdown time	$\leq 50$	ns
Maximum switching frequency	200	Hz
Maximum loading current	50	mA
Weight	~ 2	g
Marking, blue	<b>EPCOS 400 WWY O</b> 400    - Nominal voltage WW    - Calendar week of production Y      - Year of production O      - Non radioactive	

<sup>1)</sup> At delivery AQL 0,65 level II, DIN ISO 2859


<sup>2)</sup> Page 2, Fig. 1 and 2

<sup>3)</sup> Page 2, Fig. 3 and 4

<sup>4)</sup> Page 2, Fig. 3 and 4, 100 % outgoing inspection


<sup>5)</sup> After storage in darkness for 30 days

**Fig. 1:** QC- test circuit (100% outgoing inspection)




DUT device under test  
 ICU ignition control unit (sensitivity 10 .. 30 µA)  
 Discharge current 10 – 20 mA



**Fig. 2:** Explanation of measurands



**Fig. 3:** QC- test circuit (sampling inspection at 25 °C)



**Fig. 4:** Explanation of measurands



Not to scale  
 Dimensions in mm  
 Non controlled document

© EPCOS AG 2002. Reproduction, publication and dissemination of this data sheet, enclosures hereto and the information contained therein without EPCOS' prior express consent is prohibited.

Purchase orders are subject to the General Conditions for the Supply of Products and Services of the Electrical and Electronics Industry recommended by the ZVEI (German Electrical and Electronic Manufacturers' Association), unless otherwise agreed.